



17833 59th Ave NE, Suite C
Arlington, WA 98223

"Built to Last"

OFFICE: (360) 403-4900
Contractor's License: HCISTS864DE

General Contractor of Pre-Engineered Steel Buildings and Steel Building Components

Roll-Up Door Retail Cost

Specifications:

- Curtain: Continuous corrugated sheet design, cold roll formed of 26 gauge high strength galvanized steel with a silicone modified polyester finish in many standard colors.
- Drum Axle Assembly: Constructed of 1-1/2" schedule 40 steel pipe with stamped steel drums continuously welded around.
- Bottom Edge: Made up of extruded aluminum alloy with a structural steel angle securely attached, and a blade of weather strip made of flexible PVC.
- Guides: Made up of extruded aluminum alloy with a durable plastic rub strip insert to provide smooth operation.
- Mounting Brackets: Made of 10 gauge steel and die formed. The bearing hub is securely welded to the bracket.
- Lock Assembly: Inside slide lock mounted on the bottom of each guide.
- **INSTALL COST: Large (above 10' tall, 10' wide) = \$600 Small: \$400 (Under 10' tall, 10' wide). \$700—MFG Install**
- Headspace needed needs to be verified. For Example: 10x10 needs 18" headroom, 5" each side & 12x14 needs 21" of headroom.

14' H	\$1,100.00	\$1,350.00	\$1,622.00	\$1,724.00
12' H	\$870.00	\$1,080.00	\$1,358.00	\$1,430.00
10' H	\$850.00	\$990.00	\$1,064.00	\$1,210.00
8' H	\$820.00	\$910.00	\$966.00	\$1,006.00
	8' W	10' W	12' W	14' W

Chain Hoist Addition:	\$170.00
Chain Hoist or Operator Prep:	\$70.00
Motor Operator:	\$1,207.50
Remote Controls (with one transmitter):	\$210.00
Insulation (Reflective) Per SF of Opening:	\$2.75
Header Seal (Per LF)	\$10.00

Any other size will need to be quoted from HCI's distributor.

These prices are for an off-white color. For different colors, contact distributor.